

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notification inviting tenders up to 2 P.M. on 8th May 1933 for the restoration of Kakaramanahalli Basavegowdankere, Reg. No. 208 of Closepet Taluk, published on page 433 of Part VI of the *Mysore Gazette*, dated 20th April 1933. The earnest money to accompany the tender is Rs. 150.

Abstract Notification.

The attention of the public is invited to the notification inviting tenders up to 2 P.M. of 8th May 1933 for the Restoration of Channels from the Aralamallige tank in Doddballapur Taluk published on pages 434 and 435 of Part VI of the *Mysore Gazette*, dated 20th April 1933. The amount of earnest money to accompany the tender is Rs. 150.

Abstract Notification, dated 21st April 1933.

The attention of the public is invited to the detailed notification calling for sealed tenders for removing the 15" and 16" Cast Iron and Steel Pipes laid from Combined Jewell Filters to "Y" Tank a distance of about 12 miles and carting the same to Combined Jewell Filters, Bangalore, published on pages 479 to 480 of Part VI of the *Mysore Gazette*, dated 27th April 1933.

The last day for the receipt of tenders is 12th May 1933.

H. F. MARKER,
Executive Engineer.

BANGALORE BUILDINGS DIVISION, BANGALORE.

Abstract Notification.

The attention of the public is invited to the notification calling for tenders for "Construction of Sanskrit College in Bangalore" published on pages 481 to 483 of part VI of the *Mysore Gazette*, dated 27th April 1933.

The last date for receiving tender is 12th May 1933.

A. TANDONI RAO,
Executive Engineer.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE,
BANGALORE.*Notification dated 26th April 1933.*

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on the 19th May 1933 for "Constructing an Office and Stores at Goribidnur Town."

1. The tenders will be opened in public at 2 P.M. on 19th May 1933. The work should be completed within three months and the monthly progress should not be less than Rs. 600.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form attached showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 150 in Government Promissory notes, as earnest money and be superscribed "Tender for Constructing an Office and Stores at Goribidnur Town".

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reasons whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marroyt's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement showing the approximate quantities of work for Constructing an Office and Stores at Goribidnur Town.

Sl. No.	Items of work	Unit	Quantity
1	Earth work excavation and filling in basement	C.yd.	31
2a	Concrete stone jelly in Lime mortar foundation	"	259
b	Coursed rubble stone masonry in mortar foundation and basement with bond stones 6' apart in every course.	"	724
c	Do in clay do	"	69
d	Burnt brick in clay superstructure	"	1,491
e	Stone slabs 4" thick roughly dressed and fixed in mortar	S.ft.	91
f	Chunam plastering 2 coats	Sqr.	28.60
g	Chunam pointing with thread lines	"	2.12
h	White and colour washing, 2 coats	"	30.72
i	Plain brick cornice 6" projection	R.ft.	65
j	Chunam patty 6" x 3" over verandah roof	"	18
k	Brick in mortar parapet wall 9" thick as per design	"	21
1	Binding wall 1 $\frac{1}{8}$ x $\frac{1}{2}$ brick in mortar and chunam plastered complete.	Brick	42
3a	Cuddapah slab flooring on 3" concrete stone jelly in mortar and cement pointed.	Sqr.	1.94
b	First class Mangalore tile flooring on 3" concrete and cement pointed.	"	3.60
c	Flooring with 3" lime concrete and cement plastering $\frac{1}{2}$ " thick.	"	0.37
4a	First class Mangalore tile roofing on Teakwood reepers 2" x 1" including wood oiling to reepers.	"	8.94
b	Roofing with Cuddapah slab terrace with Cuddapah slabs 1 $\frac{1}{2}$ " thick, 3" thick concrete, 2 layers of flat tiles and surface plastered and ceiling cement pointed and white washed.	"	0.44
c	Ridge tiles set in mortar and cement point	R.ft.	28
d	Teakwood work with wood oiling 2 coats	Cft.	37.46
5	Steel work fixed complete	Cwt.	3.79
6a	Teakwood doors panelled 1 $\frac{1}{2}$ " shutters with fixtures, etc., complete.	S.ft	74
b	Teakwood windows with glazed shutters 1 $\frac{1}{2}$ " thick and iron bars, etc., complete.	"	87.5
c	Teakwood rectangular ventilators with glazed shutters, etc.	"	14
d	Teakwood eve board plain 8" x $\frac{1}{2}$ " fixed complete	R.ft.	55
7	Chocolate painting 2 coats	Sqr.	3.9
8	Wire gauze shutters fixed complete as per design	S.ft.	63
9	Rain water down pipe 3" dia. fixed complete	R.ft.	10

Notification, dated 26th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 p.m. on the 19th May 1933, for "Constructing an Office and Stores at Malur Town."

1. The tenders will be opened in public at 2 p.m. on 19th May 1933. The work should be completed within three months and the monthly progress should not be less than Rs. 600.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form attached showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 150 in Government Promissory Notes as earnest money and be superscribed "Tender for Constructing an Office and Stores at Malur Town."

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board on the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marroyt's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement showing the approximate quantities of work for Constructing an Office and Stores at Malur Town.

Sl. No.	Items of work	Unit	Quantity
1	Earth work excavation and filling in basement	Cyd.	31
2a	Concrete stone jelly in lime mortar foundation	"	259
b	Coursed rubble stone masonry in mortar foundation and basement with bond stones 6' apart in every course.	"	724
c	Do in clay do	"	69
d	Burnt brick in clay superstructure	"	1,491
e	Stone slabs 4" thick roughly dressed and fixed in mortar	S.ft.	91
f	Chunam plastering 2 coats	Sqr.	28'60
g	Chunam pointing with thread lines	"	2'12
h	White and colour washing 2 coats	"	30'72
i	Plain brick cornice 6" projection	R.ft.	65
j	Chunnam party 6" x 3" over verandah roof	"	18
k	Brick in mortar parapet wall 9" thick as per design	"	21
l	Binding wall 1 1/8" x 1/2" brick in mortar and chunam plastered complete.	Brick	42
3a	Cuddapah slab flooring on 3" concrete stone jelly in mortar and cement pointed.	"	1'94
b	First class Mangalore tile flooring on 3" concrete and cement pointed.	Sqr.	3'60
c	Flooring with 3" lime concrete and cement plastering 1/2" thick	"	0'37
4a	First class Mangalore tile roofing on T. W. reepers 2" x 1" including wood oiling to reepers.	"	8'94
b	Roofing with Cuddapah slab terrance with Cuddapah slabs 1 1/2" thick, 3" thick concrete, 2 layers of flat tiles and surface plastered and ceiling cement pointed and white washed.	"	0'44

Sl No.	Items of work	Unit	Quantity
c	Ridge tiles set in mortar and cement pointed ...	R.ft.	28
d	Teakwood work with wood oiling 2 coats ...	C.ft.	37 46
5	Steel work fixed complete ...	Cwt.	379
6a	Teakwood doors panelled, $\frac{1}{2}$ " shutters with fixtures, etc., complete	S.ft.	74
b	Teakwood windows with glazed shutters $1\frac{1}{4}$ " thick and iron bars, etc., complete.	"	87.5
c	Teakwood rectangular ventilators with glazed shutters, etc. ...	"	14
d	Teakwood eve board plain 8" x $\frac{3}{4}$ " fixed complete ...	R.ft.	55
7	Chocolate painting 2 coats ...	Sqr.	390
8	Wire gauze shutters fixed complete as per design ...	S.ft.	63
9	Rain water down pipe 3" dia. fixed complete ..	R.ft.	10

C. M. CARIAPA,
Chief Electrical Engineer.

KOLAR DIVISION.

Abstract Notification, dated 17th April 1933.

The attention of the public is invited to the advertisement published in page 464, of Part VI of the *Mysore Gazette*, dated 27th April 1933, calling for tenders for the work of restoring Alagurki Chikkamanakere, Registered No. 110 of Sidlaghatta Taluk.

The last date fixed for receipt of tender in this office is 15th May 1933 up to 2 p.m.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Notification, dated 21st April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 1 p.m., on 22nd May 1933, for restoring Khayamgutta Hadaghatta Oorimundinkere Minor Tank, Registered No. 22 of Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1935:—

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Khayamgutta Hadaghatta Minor Tank, Registered No. 22, Mandya Taluk" in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. In all cases of disputes, the decision of the Executive Engineer will be final and legally binding.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.